

**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**

---

GRANTING A SPECIAL MANAGEMENT AREA MAJOR PERMIT TO ALLOW FOR THE CONSTRUCTION OF A NEW TWO-STORY STRUCTURE WITH A PRIMARY DWELLING UNIT ON THE SECOND FLOOR, ATTACHED ACCESSORY DWELLING UNIT ON THE GROUND FLOOR, CARPORT, AND FENCE IN HAU'ULA, O'AHU.

WHEREAS, on April 29, 2024, the Department of Planning and Permitting ("DPP") accepted the application (File No. 2024/SMA-25) of HI Home Buyer Group (the "Applicant") for a Special Management Area ("SMA") Major Permit to allow for the construction of a new two-story structure with a three-bedroom primary dwelling unit with covered lanai on the second floor, attached two-bedroom accessory dwelling unit on the ground floor, carport, and perimeter fence on approximately 5,064 square feet of land zoned R-5 Residential District, located at 54-84 Kamehameha Highway in Hau'ula, and identified as Tax Map Key 5-4-001:048 (the "Project"); and

WHEREAS, on June 28, 2024, the DPP held a public hearing at the Fasi Municipal Building 6th Floor Conference Room, which was attended by the Applicant's Agent and DPP staff; no members of the public attended, no verbal testimony was offered, and no written testimony was received; and

WHEREAS, on August 12, 2024, within 45 calendar days after the close of the public hearing, the DPP, having duly considered all evidence and the objectives, policies, and guidelines, as established in §§ 25-3.1 and 25-4.1, Revised Ordinances of Honolulu 2021 ("ROH"), and §§ 205A-2 and 205A-26, Hawaii Revised Statutes ("HRS"), completed its report and transmitted its findings and recommendation of approval to the City Council ("Council"); and

WHEREAS, the Council, having received the findings and recommendation of the DPP on August 14, 2024 by Departmental Communication 600 (2024), and having duly considered all of the findings and reports on the matter, desires to approve the subject application for an SMA Major Permit, subject to the conditions enumerated below; now, therefore,

BE IT RESOLVED by the Council of the City and County of Honolulu that an SMA Major Permit be issued to the Applicant for the Project, subject to the following conditions:

- A. Development must be in general conformity with the Project as described in the DPP's findings and recommendation, referenced above, and as depicted in Exhibits A, B, C-1 through C-8, and D through J, attached hereto and incorporated



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**


---

by reference herein. Any change in the size or nature of the Project that may have a significant effect on coastal resources addressed in ROH Chapter 25 or HRS Chapter 205A, or both, will require a new application and SMA Major Permit. Any change that does not have a significant effect on coastal resources will be considered a minor modification and may be permitted under this resolution, upon review and approval by the DPP Director.

- B. The Project's building permit application must include revised plans showing grasscrete, grass block pavers, or other pervious pavement used for the driveway and any other proposed paved unroofed areas. If the area under the elevated structure is paved, pervious material must be used under the elevated structure.
- C. To account for the potential shift of land from the State Land Use Urban District to the State Land Use Conservation District due to anticipated coastal erosion, the landowner hereby acknowledges (and any successor owner or interested party is hereby notified of) the following:

*"In choosing to implement construction activities at Tax Map Key 5-4-001:048, the landowner hereby acknowledges that land makai of the regulatory shoreline is State public land, falls within the State Land Use Conservation District, and must remain available for public use and recreational activities. The landowner further acknowledges that should any portion of a structure encroach into State public land, the State Board of Land and Natural Resources may require the removal of the structure or a lease for the encroachments extending into the State public land. As a result of this acknowledgement, successor owners and interested parties are hereby notified of this same information and the landowner shall hold harmless and indemnify the City for any responsibility that may result from adverse impacts associated with sea level rise and coastal erosion."*

This statement must be clearly stated under "Landowner Acknowledgements" on all Project building permit plans.



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**

---

- D. Following approval of this SMA Major Permit, neither the current landowner, nor any successor owner or interested party, may claim hardship due to erosion, sea level rise, or any other coastal hazard, in order to obtain approval for a Shoreline Setback Variance for a new shoreline protection structure. The landowner hereby acknowledges (and any successor owner or interested party is hereby notified of) the following:


*"In choosing to undertake the development at Tax Map Key 5-4-001:048, the landowner hereby acknowledges that no claim of hardship due to erosion, sea level rise, or any other coastal hazard may be asserted in order to obtain approval for a Shoreline Setback Variance for a new shoreline protection structure."*

This statement must be clearly stated under "Landowner Acknowledgements" on all Project building permit plans.

- E. To minimize the potential for adverse impacts related to coastal hazards, including but not limited to sea level rise, coastal erosion, flooding, wave action, and storm surge, the landowner hereby acknowledges (and any successor owner or interested party is hereby notified of) the following:

1. *"The landowner hereby acknowledges that Tax Map Key 5-4-001:048 is susceptible to coastal hazards, which may result in harm to or loss of life and property."*
2. *"The landowner hereby acknowledges that the Tax Map Key 5-4-001:048 may be adversely impacted by coastal hazards. The landowner agrees to assume all risk and liability for any harm to or loss of life and property due to development in close proximity to the shoreline. The landowner further agrees to accept all responsibility for the cost and physical removal of materials and structures lost or damaged as a result of coastal hazards, including the cleanup and restoration of the Project site."*

The statements enumerated in this condition must be clearly stated under "Landowner Acknowledgements" on all Project building permit plans.



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**

---

- F. To ensure the Applicant is aware that bed and breakfast homes and transient vacation units are not allowed on the Project site, the landowner hereby acknowledges (and any successor owner or interested party is hereby notified of) the following:

*"The landowner hereby acknowledges that bed and breakfast homes and transient vacation units, as those terms are defined in ROH Chapter 21, the Land Use Ordinance, are not allowed on Tax Map Key 5-4-001:048."*


This statement must be clearly stated under "Landowner Acknowledgements" on all Project building permit plans.

- G. To minimize impacts to archaeological, historic, or cultural resources that may be present on the Project site, if, during construction, any previously unidentified archaeological sites or remains (such as artifacts; shell, bone, or charcoal deposits; human burials; rock or coral alignments; pavings; or walls) are encountered, the Applicant shall stop work, protect the find from further disturbance, and contact the State Historic Preservation Division ("SHPD") immediately. Work in the immediate area must be stopped until SHPD has assessed the impact and has made further recommendations for mitigative activity.

The requirement in this condition must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

- H. To minimize impacts to endangered, protected, or threatened avian, marine, and terrestrial fauna that may frequent or traverse the vicinity of the Project site, the Applicant is responsible for the following:

1. All new and replacement outdoor light fixtures must not exceed a color temperature of 3,000 degrees kelvin;
2. Artificial light from exterior light fixtures on the Project site, including but not limited to floodlights, uplights, or spotlights used for decorative or aesthetic purposes, is prohibited if the light directly illuminates, or is directed across property boundaries toward, the shoreline and ocean waters, except as may otherwise be permitted pursuant to HRS § 205A-71(b);



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**

---


3. Exterior light fixtures on the Project site must be fully shielded using full cutoff fixtures with the light directed downward so that the light bulb is only visible from below the light fixture;
4. All Project site work and construction activities are limited to daylight hours (sunrise to sunset);
5. Barbless fencing must be used for all fence construction to avoid the entanglement of Hawaiian hoary bats; and
6. Woody plants greater than 15 feet in height may not be disturbed, removed, or trimmed during the Hawaiian hoary bat birthing and pup rearing season (June 1 through September 15).

The requirements enumerated in this condition must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

**I. The Applicant shall obtain a construction permit or building permit for the Project within 36 months after the effective date of this SMA Major Permit.**

Failure to obtain a construction permit or building permit within this period will render this SMA Major Permit null and void; provided that this period may be extended as follows:

1. The DPP Director may extend this period if the Applicant demonstrates good cause; provided that the DPP Director may not extend the period beyond one year from the initial deadline set by the Council.
2. If the Applicant demonstrates good cause for an extension exceeding one year, the DPP Director shall prepare and submit to the Council a report on the proposed extension, which must include the DPP Director's findings and recommendations thereon. The Council may approve the proposed extension, or approve an extension for a shorter or longer period, or deny the proposed extension, by adoption of a committee report or resolution.
3. If the Council fails to take final action on the proposed extension within the first to occur of:



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---


**RESOLUTION**

---

- a. Sixty days after receipt of the DPP Director's report; or
- b. The Applicant's then-existing deadline for obtaining a construction permit or building permit,

the extension will be deemed to be denied.

- J. Approval of this SMA Major Permit does not constitute compliance with other City ordinances, including but not limited to the Land Use Ordinance ("LUO") and building and construction codes, or other governmental requirements, including but not limited to LUO-related approvals, and building, grading, and grubbing permit approvals, which are subject to separate review and approval. The Applicant is responsible for ensuring that the final plans for the Project approved under this SMA Major Permit comply with all applicable City ordinances and other governmental provisions and requirements; and



**HONOLULU CITY COUNCIL**  
**KE KANIHELA O KE KALANA O HONOLULU**  
CITY AND COUNTY OF HONOLULU

No. 24-208, CD1

---

**RESOLUTION**

---

BE IT FINALLY RESOLVED that copies of this resolution be transmitted to the HI Home Buyers Group and Mark Howland, WHALE Environmental Services, P.O. Box 455, Kahuku, Hawai'i, 96731; Dawn Takeuchi Apuna, Director of Planning and Permitting, 650 South King Street, 7th Floor, Honolulu, Hawai'i 96813; and Mary Alice Evans, Director of the State Office of Planning and Sustainable Development, Attention: Coastal Zone Management Branch, P.O. Box 2359, Honolulu, Hawai'i 96804-2359.

INTRODUCED BY:

Tommy Waters (br)

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

DATE OF INTRODUCTION:



\_\_\_\_\_

\_\_\_\_\_

August 14, 2024  
Honolulu, Hawai'i

\_\_\_\_\_

Councilmembers



## EXHIBIT A LOCATION MAP

FILE NO. 2024/SMA-25



TAX MAP KEY 6-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu




## EXHIBIT B ZONING MAP

FILE NO. 2024/SMA-25

TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu



# EXHIBIT C-2




|     |         |                      |
|-----|---------|----------------------|
| NO. | DATE    | DESCRIPTION          |
| 1   | 10/1/20 | ISSUED FOR PERMIT    |
| 2   | 10/1/20 | REVISED PER COMMENTS |
| 3   | 10/1/20 | REVISED PER COMMENTS |
| 4   | 10/1/20 | REVISED PER COMMENTS |
| 5   | 10/1/20 | REVISED PER COMMENTS |
| 6   | 10/1/20 | REVISED PER COMMENTS |
| 7   | 10/1/20 | REVISED PER COMMENTS |
| 8   | 10/1/20 | REVISED PER COMMENTS |
| 9   | 10/1/20 | REVISED PER COMMENTS |
| 10  | 10/1/20 | REVISED PER COMMENTS |

HI HOME BUYERS GROUP  
 DEMO EXISTING SF DWELLING FOR NEW  
 ADU & NEW SF DWELLING ABOVE  
 5444 KAN HWY KANSAS, MO 66217  
 54-001-048

## EXTERIOR ELEVATIONS


A104

|     |         |                      |
|-----|---------|----------------------|
| NO. | DATE    | DESCRIPTION          |
| 1   | 10/1/20 | ISSUED FOR PERMIT    |
| 2   | 10/1/20 | REVISED PER COMMENTS |
| 3   | 10/1/20 | REVISED PER COMMENTS |
| 4   | 10/1/20 | REVISED PER COMMENTS |
| 5   | 10/1/20 | REVISED PER COMMENTS |
| 6   | 10/1/20 | REVISED PER COMMENTS |
| 7   | 10/1/20 | REVISED PER COMMENTS |
| 8   | 10/1/20 | REVISED PER COMMENTS |
| 9   | 10/1/20 | REVISED PER COMMENTS |
| 10  | 10/1/20 | REVISED PER COMMENTS |



3 31'8\"/>

1 FRONT ELEVATION  
31'8\"/>



4 RIGHT ELEVATION  
31'8\"/>

2 RIGHT ELEVATION  
31'8\"/>




EXHIBIT C-4

**GroundUp**  
 (800) 628-4111  
 10000 Highway 19, Suite 200  
 Houston, TX 77058




| NO. | REVISION          | DATE       |
|-----|-------------------|------------|
| 1   | ISSUED FOR PERMIT | 08/15/2024 |

HI HOME BUYERS GROUP  
 DEMO EXISTING SF DWELLING FOR NEW  
 ADU & NEW SF DWELLING ABOVE  
 5441 KAH KAH WAY, HOUSTON, TX 77057  
 24-001-048

NEW FLOOR PLANS

|              |                      |
|--------------|----------------------|
| Sheet No.    | A101                 |
| Project Name | HI HOME BUYERS GROUP |
| Client       | HI HOME BUYERS GROUP |
| Architect    | GroundUp             |
| Engineer     | GroundUp             |
| Scale        | 1/8" = 1'-0"         |





(800) 623-6119  
Kalamazoo, MI 49001

Kendall, M. 1973.

[illegible]

HI HOME BUYERS GROUP

DEMO EXISTING SF DWELLING FOR NEW  
ADU & NEW SF DWELLING ABOVE

54-34 X-101 NEW MEXICO, IN 0017

[illegible]

## FOUNDATION PLAN

|                     |                         |
|---------------------|-------------------------|
| Date                | Issue Date              |
| Dissemination Point | Construction Guidelines |
| Controlled by       | Classifier              |
| <h1>S001</h1>       |                         |
| Grade               | 1.00 = 1.00             |

### FOUNDATION LEGEND

- F-1 2'-0" X 2'-0" X 1'-0" FOOTING W/ 3-#4 EA. WAY
- F-2 2'-6" X 2'-6" X 1'-0" FOOTING W/ 4-#4 EA. WAY
- F-3 3'-6" X 3'-6" X 1'-2" FOOTING W/ 6-#4 EA. WAY
- F-4 5'-3" X 5'-3" X 1'-0" FOOTING W/ 7-#4 EA. WAY

- F-2 2'-6" X 2'-6" X 1'-0" FOOTING W/ 4-#4 EA. WAY

- F-3 3'-5" X 3'-6" X 1'-2" FOOTING W/ 8-#4 EA. WAY

- F-4 5'-3" X 5'-3" X 1'-0" FOOTING W/ 7-#4 EA. WAY


## EXTENT OF FRAMING

**(2) PLAIN**

222 @ 18 O.C. JOISTS

4" THICK 2.0 G W/ EXT-  
MR. 30M.4 W/WM AT  
BLAS MID-DEPTH OVER  
5 MIL VAPOR BARRIER  
OVER 4" GRAVEL FILL

5" THICK S.O.O. WE EMB-  
LEASING 4 WAGON AT  
MILAS MED-DEPTH OVER  
OVER 4" GRAVEL FILL



① FOUNDATION PLAN  
SCALE = 1"=8'


1.18

# INDIVIDUAL WASTEWATER SYSTEM FOR NEW RESIDENCE 54-84 KAMEHAMEHA HWY. HAUULA, HI 96717 TMK: (1) 5-4-001:048

## INSTALLATION NOTES:

1. CONNECT TO EXISTING LINE FROM DWELLING. MAINTAIN MIN. 2% SLOPE TO SEPTIC TANK.
2. INSTALL CLEANOUT TO GRADE. SEE DETAIL ON SHEET C-2.
3. INSTALL 4" DIA. 40' PVC RISER AND NEC. FITTINGS. MAINTAIN MIN. 2% SLOPE INTO CUT OF SEPTIC TANK. INSTALL 4" DIA. 1' LIFT HOLE LOW PRESSURE PIPE AND NEC. FITTINGS FROM SEWAGE LIFT STATION TO DISTRIBUTION BOX. MAINTAIN MIN. 1% COVER. SEE DETAIL ON SHEET C-2.
4. INSTALL 1,250-GALLON PRECAST CONCRETE DUAL COMPARTMENT SEPTIC TANK, BASED PRECAST MODEL M1250ST. SEE DETAIL ON SHEET C-2.
5. INSTALL DUPLEX SEWAGE LIFT STATION WITH CONCRETE BUILT-IN/ACT. COUNTERWEIGHT. HOPE PUMP BASIN, GRINDER PUMPS 2 BA, 1 HP, 1/8" VPI, 60 HZ, 1/2" FLANGE, BALL VALVE, CHECK VALVE, FLAT TIE, NEC. PIPE/FITTINGS, AND COVER. SEWAGE LIFT STATION COMPONENTS SHALL BE QUALITY ENGINEERED PRODUCTS OR APPROVED EQUAL. SEE DETAILS ON SHEET C-3 AND C-4.
6. INSTALL DUPLEX SEWAGE LIFT STATION CONTROL PANEL, 110V, 1 HP, IN MEDIA 4X ENCLOSURE. MOUNT TO WALL OF DWELLING. CONNECT 110V POWER FROM DWELLING TO CONTROL PANEL.
7. INSTALL 4-HOLE DISTRIBUTION BOX, TIE-TITE BR22, PLUG ONE OUTLET. SEE DETAIL ON SHEET C-3.
8. MOUND ABSORPTION BED: 12' x 25' @ 300 SF, INSTALL 4 ROWS OF QUICK INFLTRATOR CHAMBERS. INSTALLED LEVEL, ADJACENT TO EACH OTHER. PROVIDE MIN. 10" TOPSOIL OVER CHAMBERS AND PLANT WITH BEACHORE PARALAUH GRASS. CONTRACTOR SHALL PROVIDE TEMPORARY IRRIGATION TO PERMANENTLY ESTABLISH GRASS ON TOP AND SLOPES OF MOUNDED ABSORPTION BED. SEE PROFILE AND SECTION DETAIL ON SHEET C-2.
9. INSTALL POWER AND CONTROL WIRING IN 1" PVC CONDUIT FROM CONTROL PANEL TO LIFT STATION. PIPE CUSHION SHALL BE NO. 4 MANUFACTURED SAND FILL AROUND ALL BENDS OF CONDUIT. PROVIDE MIN. 12" COVER.
10. REMOVE ALL LARGE TREES WITHIN 10' OF ABSORPTION BED AND 2' OF 4" PVC TANK.
11. MAINTAIN MIN. 10' CLEARANCE AROUND SEPTIC TANK AND/OR ABSORPTION BED.
12. SEPTIC TANK AND ABSORPTION BED BEED TO ACCOMMODATE UP TO 3 BEDROOMS.

| DRAWING INDEX |           |                                  |
|---------------|-----------|----------------------------------|
| DRAWING NO.   | SHEET NO. | DESCRIPTION                      |
| C-1           | 1         | SITE PLAN                        |
| C-2           | 2         | ABSORPTION BED PROFILE & SECTION |
| C-3           | 3         | DETAILS                          |
| C-4           | 4         | SEWAGE LIFT STATION DETAIL       |
|               | 5         | FLOOR PLANS                      |



SITE PLAN



INDIVIDUAL WASTEWATER SYSTEM  
FOR NEW RESIDENCE  
54-84 KAMEHAMEHA HWY.


SITE PLAN

|             |         |          |           |
|-------------|---------|----------|-----------|
| DESIGNED BY | DATE    | SCALE    | REVISIONS |
| PROJECT NO. | 10/2022 | AS SHOWN |           |
| CHECKED BY  |         |          |           |
| APPROVED BY |         |          |           |


4-14

C-1

**EXHIBIT C-7**



**FOUNDED ABSORPTION BED PROFILE**  
**(NOT TO SCALE)**





**FOUNDED ABSORPTION BED SECTION**  
**(NOT TO SCALE)**

**MOUNDED ABSORPTION BED AND TRENCH SECTION NOTES:**

1. SCARIFY AND REMOVE MIN. TOP 6" OF EXISTING GRADE BELOW ABSORPTION BED, GRADE LEVEL.
2. PROVIDE MIN. 3.0" SUITABLE SOIL W/ A MAX. PERCOLATION RATE OF 60 MIN/IN.
3. PERCOLATION RATE USED FOR SIZING ABSORPTION BED: 1" MIN/IN. (HAR 11-82, APP. D, TABLE III): 70 SF/BEDROOM.
3. NATIVE SANDY SOIL BELOW BOTTOM OF ABSORPTION BED SHALL BE CONDITIONED WITH APPROXIMATELY 1:1 RATIO OF SAND TO IMPORTED SOIL CONTAINING FINES SUFFICIENT TO ACHIEVE A MINIMUM PERCOLATION RATE OF 1 MIN/IN. CONDITIONED SOIL MIX SHALL EXTEND MIN. OF 3" BELOW BOTTOM OF ABSORPTION BED.
4. CHAMBERS SHALL BE PLACED DIRECTLY ON NATIVE SAND/IMPORTED SOIL MIX.
5. CONTRACTOR SHALL PROVIDE AND MAINTAIN TEMPORARY IRRIGATION SYSTEM TO PERMANENTLY ESTABLISH GROWTH OF SEASONAL PAPALUMP GRASS.
6. THE BOTTOM OF THE ABSORPTION BED SHALL NOT BE COMPACTED.
7. BACKFILL MATERIAL OVER SOLID PVC PIPE MAY BE ON-SITE MATERIAL.
8. PIPE BEDDING MATERIAL SHALL BE 3/4" BASE COURSE.

[illegible]





## EXHIBIT D FLOOD MAP

FILE NO. 2024/SMA-25



TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu




## EXHIBIT E WETLAND MAPPER

FILE NO. 2024/SMA-25



TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

August 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu




## EXHIBIT F SOILS MAP

FILE NO. 2024/SMA-25

TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu

# EXHIBIT G STORM SURGE MAP











**EXHIBIT H**  
**SEA LEVEL RISE EXPOSURE MAP**





# **EXHIBIT I TSUNAMI EVACUATION MAP**

FILE NO. 2024/SMA-25



TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
Land Use Permits Division  
City and County of Honolulu




# **EXHIBIT J** **CUMULATIVE PROJECT** **RADIUS MAP** **(WITHIN 500 FEET)**

FILE NO. 2024/SMA-25

TAX MAP KEY 5-4-001: 048

54-84 KAMEHAMEHA HWY - HAU'ULA

July 2024



Department of Planning and Permitting  
 Land Use Permits Division  
 City and County of Honolulu

CITY COUNCIL  
CITY AND COUNTY OF HONOLULU  
HONOLULU, HAWAII  
CERTIFICATE

RESOLUTION 24-208, CD1

Introduced: 08/14/24 By: TOMMY WATERS - BY REQUEST Committee: ZONING (ZON)

Title: GRANTING A SPECIAL MANAGEMENT AREA MAJOR PERMIT TO ALLOW FOR THE CONSTRUCTION OF A NEW TWO-STORY STRUCTURE WITH A PRIMARY DWELLING UNIT ON THE SECOND FLOOR, ATTACHED ACCESSORY DWELLING UNIT ON THE GROUND FLOOR, CARPORT, AND FENCE IN HAU'ULA, O'AHU.


Voting Legend: \* = Aye w/Reservations

|          |       |                                                                                       |
|----------|-------|---------------------------------------------------------------------------------------|
| 08/14/24 | INTRO | Introduced.                                                                           |
| 09/25/24 | ZON   | Reported out for adoption as amended in CD1 form.                                     |
|          |       | CR-288                                                                                |
|          |       | 4 AYES: CORDERO, DOS SANTOS-TAM, SAY, WEYER                                           |
|          |       | 1 ABSENT: KIA'ĀINA                                                                    |
| 10/09/24 | CCL   | Committee report and Resolution as amended were adopted.                              |
|          |       | 9 AYES: CORDERO, DOS SANTOS-TAM, KIA'ĀINA, OKIMOTO, SAY, TULBA, TUPOLA, WATERS, WEYER |

I hereby certify that the above is a true record of action by the Council of the City and County of Honolulu on this RESOLUTION.



*f* GLEN I. TAKAHASHI, CITY CLERK



TOMMY WATERS, CHAIR AND PRESIDING OFFICER