REPORT OF THE COMMITTEE ON ZONING & PLANNING

Voting Members:
Esther Kia'āina, Chair; Tommy Waters, Vice-Chair;
Radiant Cordero, Val A. Okimoto, Andria Tupola

Committee Meeting Held
February 5, 2026

Honorable Tommy Waters
Chair, City Council
City and County of Honolulu

Mr. Chair:

Your Committee on Zoning & Planning, which considered Resolution 26-4 entitled:

"RESOLUTION GRANTING A SPECIAL MANAGEMENT AREA MAJOR PERMIT TO ALLOW FOR THE REHABILITATION AND UPGRADE OF THE WEST LOCH WASTEWATER PUMP STATION IN HONOULIULI, O'AHU,"

transmitted by Departmental Communication 6 (2026), dated January 5, 2026, from the Department of Planning and Permitting ("DPP"), and introduced on January 7, 2026, reports as follows:

The purpose of Resolution 26-4 is to grant a Special Management Area ("SMA") Major Permit to the Department of Environmental Services (the "Applicant") to allow for the expansion and rehabilitation of the existing West Loch wastewater pump station ("WWPS"), including the construction of a new generator room attached to the WWPS building by a breezeway; relocation of various equipment and systems to the new generator room; removal and replacement of an above-ground diesel fuel storage tank; relocation of the north and east concrete rubble masonry perimeter walls; replacement of submersible pumps, pump bypass system, force main piping and valves, ventilation systems, restroom facilities, windows, doors, and gates; installation of a new air relief valve; expansion and rehabilitation of the wet well; construction of a new trash enclosure; and restriping of the surface parking area, on an approximately 2,300-square-foot portion of an 80.269 acre zoning lot that is split-zoned AG-1 Restricted Agricultural District and P-2 General Preservation District (the 2,300-square foot site is within the AG-1 District), located at 91-1024 Kapapapuhi Street in Honouliuli, and identified as a portion of Tax Map Key 9-1-181:001 (the "Project").

ADOPTED ON FEB 18 2026

COMMITTEE REPORT NO. 36(26)

The 2,300-square-foot Project site is located on a portion of the West Loch golf course parcel. The golf course and the West Loch WWPS were developed by the City in the late 1980s as a part of the West Loch Estates subdivision. The West Loch WWPS has a capacity of 1,050 million gallons per day, and pumps wastewater from the West Loch subdivision through a force-main along the Pearl Harbor shoreline to a manhole in the Waipahu industrial area. The wastewater then flows via gravity line to the Kunia wastewater pump station, and to the Honouliuli wastewater treatment plant.

The large 80-acre zoning lot is not a shoreline lot, but it is technically considered a shoreline lot because portions of the zoning lot are within the 60-foot shoreline setback area. However, the Project site is more than 400 feet from the shoreline, and is not expected to be impacted by 3.2 feet of sea level rise by the year 2100.

An environmental assessment ("EA") was completed for the Project, and the Department of Environmental Services issued a finding of no significant impact on May 28, 2025. The EA included a literature review and field inspection ("LRFI") conducted on October 2, 2024, by Keala Pono Archaeological Consulting LLC ("Keala Pono").

There are many archaeological studies prepared in response to recent development in the area. Pre-contact sites near the Project site include fishing shrines and fishponds, iwi kūpuna (Native Hawaiian ancestral remains), habitation areas, and agricultural sites. Post-contact sites are associated with the historic sugar plantation era, and include foundations of former plantation structures, historic burials, irrigation features, wells, and remnants of the Oahu Railway and Land Company railroad. There were nearly 100 Land Commission awards for lo'i kalo (traditional Hawaiian flooded or irrigated fields specifically for growing taro). Based on the cultural sensitivity of the area, Keala Pono recommended the preparation of an archaeological monitoring plan ("AMP").

In November 2025, Keala Pono prepared a cultural impact assessment ("CIA") and Ka Pa'akai analysis for the Project site. While the CIA and Ka Pa'akai analysis did not identify cultural resources or ongoing traditional cultural practices on the Project site, fishing and crabbing as well as fishpond and wetland habitat restoration are ongoing practices nearby. Like the LRFI, the CIA recommended archaeological monitoring. Condition B of the proposed CD1 includes conditions requiring the Applicant to submit to the DPP a copy of the SHPD's written acceptance of the Project's AMP, and to implement all mitigation protocols approved or otherwise required by SHPD.

The Project proposes to excavate approximately 65 cubic yards of soil material, which will be removed and disposed of offsite. While no importation of soil or structural fill material is proposed, since construction equipment may transfer invasive pathogens, pests, or plants, the proposed CD1 includes Condition D, which requires the Applicant to comply with certain protocols to minimize the spread of invasive species.

Your Committee notes that the DPP, after a public hearing held on November 7, 2025, recommends approval of the SMA Major Permit, subject to the conditions set forth in the Resolution.

At your Committee's meeting on February 5, 2026, the Applicant's agent provided a brief presentation of the Project, and responded to questions from Councilmembers.

The DPP Director testified in support of the proposed CD1 version of the Resolution.

Your Committee received no verbal or written public testimony on the Resolution.

Your Committee has carefully reviewed the conditions recommended by the DPP for inclusion in this SMA Major Permit. Although your Committee generally finds the DPP's proposed conditions to be appropriate, your Committee recommends that certain conditions be amended or added as discussed below.

Your Committee has prepared a CD1 version of the Resolution that makes the following amendments:

A. Amends the resolution title to read as follows:

"GRANTING A SPECIAL MANAGEMENT AREA MAJOR PERMIT TO ALLOW FOR THE EXPANSION AND REHABILITATION OF THE WEST LOCH WASTEWATER PUMP STATION IN HONOULIULI, O'AHU."

B. Amends the first WHEREAS clause to clarify the description of the Project and Project site.

C. Amends the third WHEREAS clause to provide that the DPP transmitted its findings and recommendation of approval to the City Council on January 5, 2026.

D. Amends the fourth WHEREAS clause to add the year of the referenced Departmental Communication.

E. In Condition B, relating to minimizing impacts to archaeological, historical, and cultural resources that may be present on the Project site:

1. Adds a new Condition B.2, requiring the Applicant to implement all mitigation protocols approved or otherwise required by SHPD, and conduct a coordination meeting with the Project's archaeological consultants and construction contractors prior to the start of construction to ensure that all appropriate persons have been informed of the mitigation protocols required by SHPD.

2. Adds that all mitigation protocols approved or otherwise required by SHPD must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

F. Amends Condition C.7, relating to conducting pre-construction nesting surveys to minimize impacts to avian fauna that may frequent or traverse the vicinity of the Project site, as follows:

1. Redesignates Condition C.7.d (relating to protocols for nests, eggs, fledglings, or downed seabirds that are discovered during Project construction) as Condition C.8;

2. Adds a new Condition C.7.d to provide that if there is a delay of three or more workdays during the active construction period, a new nest survey must be conducted before work may resume; and

3. Adds a new Condition C.7.e to provide that prior to the commencement of any ground-disturbing or construction activities, and upon the arrival of any new workers to the Project site, the Applicant, or their designated representative, must instruct all onsite Project workers to review seabird protection information provided by the DLNR DOFAW.

G. Amends Condition D.6 to delete the last sentence regarding existing palm trees becoming damaged by the coconut rhinoceros beetle.

H. Amends the BE IT FINALLY RESOLVED clause to add the Director of Parks and Recreation as a recipient of the resolution.

I. Makes miscellaneous technical and nonsubstantive amendments.

Your Committee finds, pursuant to § 205A-26, Hawaii Revised Statutes ("HRS"), and § 25-4.1, Revised Ordinances of Honolulu 2021 ("ROH"), and in agreement with the conclusion of the DPP in Departmental Communication 6 (2026), that:

1. The development, as conditioned, will not have any substantial adverse environmental or ecological effect, either alone or cumulatively with other projects.

2. The development, as conditioned, is consistent with the objectives and policies set forth in HRS § 205A-2 and ROH § 25-3.1, and the review guidelines contained in HRS § 205A-26 and ROH § 25-4.1.

3. The development, as conditioned, is consistent with the County General Plan, development plans, zoning, and other applicable ordinances.

Your Committee further finds that based on efforts to identify whether there are cultural, historic, or natural resources, or Native Hawaiian traditional and customary rights on the Project site, the Council is not aware of any existing cultural, historic, or natural resources, or Native Hawaiian traditional and customary practices on the Project site.

REPORT OF THE COMMITTEE ON ZONING & PLANNING

Voting Members:
Esther Kia'āina, Chair; Tommy Waters, Vice-Chair;
Radiant Cordero, Val A. Okimoto, Andria Tupola

Your Committee on Zoning & Planning is in accord with the intent and purpose of Resolution 26-4, as amended herein, and recommends its adoption in the form attached hereto as Resolution 26-4, CD1. (Ayes: Cordero, Kia'āina, Okimoto, Tupola, Waters – 5; Noes: None.)

Respectfully submitted,

Esther Kia'aina

Committee Chair

ADOPTED ON FEB 18 2026

COMMITTEE REPORT NO. 36(26)

HONOLULU CITY COUNCIL

KE KANIHELA O KE KALANA O HONOLULU

CITY AND COUNTY OF HONOLULU

No. **26-4, CD1**

RESOLUTION

GRANTING A SPECIAL MANAGEMENT AREA MAJOR PERMIT TO ALLOW FOR THE EXPANSION AND REHABILITATION OF THE WEST LOCH WASTEWATER PUMP STATION IN HONOULIULI, O'AHU.

WHEREAS, on September 12, 2025, the Department of Planning and Permitting ("DPP") accepted the application (File No. 2025-SMA-75) from the Department of Environmental Services (the "Applicant") for a Special Management Area ("SMA") Major Permit to allow for the expansion and rehabilitation of the existing wastewater pump station ("WWPS"), including the construction of a new generator room attached to the WWPS building by a breezeway; relocation of various equipment and systems to the new generator room; removal and replacement of an above-ground diesel fuel storage tank; relocation of the north and east concrete rubble masonry perimeter walls; replacement of submersible pumps, pump bypass system, force main piping and valves, ventilation systems, restroom facilities, windows, doors, and gates; installation of a new air relief valve; expansion and rehabilitation of the wet well; construction of a new trash enclosure; and restriping of the surface parking area, on an approximately 2,300-square-foot portion of an 80.269 acre zoning lot that is split-zoned AG-1 Restricted Agricultural District and P-2 General Preservation District (the 2,300-square-foot site is within the AG-1 Restricted Agricultural District), located at 91-1024 Kapapapuhi Street, and identified as a portion of Tax Map Key 9-1-181:001 (the "Project"); and

WHEREAS, on November 7, 2025, the DPP held a public hearing on the application at the Frank F. Fasi Municipal Building, Sixth Floor Conference Room, which was attended by the Applicant, the Applicant's agent, and DPP staff members; no members of the public attended the hearing; and

WHEREAS, on January 5, 2026, within 60 calendar days after the close of the public hearing (the Applicant having requested an extension of the 45-calendar-day administrative deadline), the DPP, having duly considered all evidence and the objectives, policies, and guidelines, as established in §§ 25-3.1 and 25-4.1, Revised Ordinances of Honolulu 2021 ("ROH"), and §§ 205A-2 and 205A-26, Hawaii Revised Statutes ("HRS"), completed its report and transmitted its findings and recommendation of approval to the City Council ("Council"); and

WHEREAS, the Council, having received the findings and recommendation of the DPP on January 6, 2026, by Departmental Communication 6 (2026) and having duly considered all of the findings and reports on the matter, desires to approve the subject application for an SMA Major Permit subject to the conditions enumerated below; now, therefore,

RESOLUTION

BE IT RESOLVED by the Council of the City and County of Honolulu that an SMA Major Permit be issued to the Applicant for the Project, subject to the following conditions:

A. Development must be in general conformity with the Project as described in the DPP's findings and recommendation, referenced above, and as depicted in Exhibits A, B, C, D-1 through D-5, E-1, E-2, F, G, H, I-1, I-2, and J through L, attached hereto and incorporated by reference herein. Any change in the size or nature of the Project that may have a significant effect on coastal resources, as addressed in ROH Chapter 25 or HRS Chapter 205A, or both, will require a new application and SMA Major Permit. Any change that does not have a significant effect on coastal resources may be considered a minor modification and may be permitted under this resolution, upon review and approval by the DPP Director.

B. To minimize impacts to archaeological, historic, and cultural resources that may be present on the Project site, the Applicant shall comply with the following.

1. Prior to the issuance of any construction permit or building permit for the Project, the Applicant shall submit to the DPP a copy of the State Historic Preservation Division's ("SHPD") written acceptance of the Project's Archaeological Monitoring Plan that meets the requirements of § 13-279-5, Hawai'i Administrative Rules.

2. The Applicant shall consult with SHPD to implement all mitigation protocols approved by SHPD under the AMP, or as otherwise required by SHPD. Prior to the commencement of ground-disturbing activity and Project construction, a coordination meeting must be conducted among the Project's archaeological consultants, the construction contractor, and applicable subcontractors to ensure that the construction contractor and applicable subcontractors have been informed of all mitigation protocols required by SHPD.

3. If, during construction, any previously unidentified archaeological sites or remains (such as artifacts; shell, bone, or charcoal deposits; iwi kūpuna (Native Hawaiian ancestral remains); rock or coral alignments; pavings; or walls) are encountered, the Applicant shall stop work, protect the find from further disturbance, and contact SHPD immediately. Work in the immediate area must be stopped until SHPD has assessed the impact and has made further recommendations for mitigative activity.

The requirements enumerated in this condition, and all mitigation protocols approved or otherwise required by SHPD, including under the AMP, must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

C. To minimize impacts to endangered, threatened, or protected avian, marine, and terrestrial fauna that may frequent or traverse the vicinity of the Project site, the Applicant is responsible for the following.

1. All new and replacement outdoor light fixtures must not exceed a color temperature of 3,000 degrees kelvin.

2. Artificial light from exterior light fixtures, including but not limited to floodlights, uplights, or spotlights used for decorative or aesthetic purposes, is prohibited if the light directly illuminates or is directed across property boundaries toward the shoreline and ocean waters, except as may otherwise be permitted pursuant to HRS § 205A-71(b).

3. Exterior light fixtures on the Project site must be fully shielded using full cutoff fixtures with the light directed downward so that the light bulb is only visible from below the light fixture.

4. All Project site work and construction activities are limited to daylight hours (sunrise to sunset).

5. Woody plants greater than 15 feet in height must not be disturbed, removed, or trimmed during the Hawaiian hoary bat birthing and pup-rearing season (June 1 through September 15).

6. Barbless fencing must be used for all fence construction to avoid the entanglement of Hawaiian hoary bats.

7. Preconstruction nesting surveys must be conducted by a qualified biologist familiar with the biology of State and federal endangered, threatened, or otherwise protected avian species, including migratory birds and Hawaiian seabirds and waterbirds, prior to and during Project construction as follows.

    a. A minimum of three days prior to the initiation of any clearing (including tree trimming or removal), grubbing, grading, excavation,

or trenching activities, the qualified biologist must conduct surveys for the presence of such bird nests, eggs, or fledglings.

b. If no nests, eggs, fledglings, or downed seabirds are discovered, work may proceed.

c. If any nests, eggs, fledglings, or downed seabirds are discovered, work may not proceed, and:

i. The United States Fish and Wildlife Service ("USFWS") and the State of Hawai'i Department of Land and Natural Resources ("DLNR") Division of Forestry and Wildlife ("DOFAW") must be contacted immediately, and a 100-foot buffer must be observed around the active nests or downed seabirds, or both, until the birds voluntarily leave the area; and

ii. Work may only resume upon implementation of any avoidance and mitigation measures recommended by the USFWS or DLNR DOFAW, or both.

d. If there is a delay of three or more workdays during the active Project construction period, before work may resume, the qualified biologist must conduct subsequent nest surveys for any new nests that Hawaiian seabirds or protected migratory birds may have attempted to establish.

e. Prior to the commencement of any ground-disturbing or construction activities, and upon the arrival of any new workers to the Project site, the Applicant, or a designated representative, must provide information to all workers who will be present at the Project site regarding the required protocols should a protected species nest or downed seabird be encountered on the Project site. All onsite Project workers must be instructed to review information provided online by the DLNR DOFAW at https://dlnr.hawaii.gov/wildlife/seabird-fallout-season/ or any successor website or information provided by the DLNR DOFAW.

8. If any nests, eggs, fledglings, or downed seabirds are discovered during Project construction, the protocols described under Condition C.7.c must be implemented.

The requirements enumerated in this condition must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

D. To minimize the spread of invasive pathogens, pests, or plants that may harm native species and ecosystems, the Applicant is responsible for the following.

1. The Applicant shall minimize the importation of fill material to the extent possible. No importation of soil or structural fill material is proposed.

2. The Applicant shall minimize the movement of plant or soil material on the Project site, and all Project construction equipment, materials, and personnel must be cleaned of excess soil and debris prior to entering and leaving a Project worksite, in accordance with the current recommendations from the O'ahu Invasive Species Committee ("OISC").

3. Prior to the commencement of any ground-disturbing or construction activities, and upon the arrival of any new workers to the Project site, a copy of the most recently updated OISC "Decontamination Protocols for Prevention of Invasive Species" ("Protocols") must be distributed to all workers who will be present at the Project site, or the Protocols must be posted on the Project site in a visible location accessible to all Project workers (including delivery and haul-out contractors), or both the distribution and posting of the Protocols is required. See https://www.oahuisc.org/print-materials/. All on-site Project workers must be instructed to review the species photos and all Protocols prior to commencing any ground-disturbing or construction activities.

4. If, at any time, species on the OISC invasive species target list website at https://www.oahuisc.org/current-targets/, or any successor website or information provided by the OISC, are discovered on the Project site, the Applicant shall immediately contact the OISC to report the discovery. The current email address and phone number for the OISC must be visibly posted at the Project site during pre-construction and construction activities. The Applicant shall implement any measures recommended by the OISC and any responsible federal or State of Hawai'i agency charged with the eradication and management of invasive species.

5. To the extent practicable, native plant species appropriate for the area must be used for new Project landscaping, with no use of invasive species. A recommended reference is the Plant Pono website at https://plantpono.org/.

6. To manage host materials and plants that may contain the coconut rhinoceros beetle at any stage of life, the Applicant shall comply with the State Department of Agriculture's Plant Quarantine Interim Rule, or any successor rule adopted by the State Department of Agriculture, that restricts the movement of coconut rhinoceros beetle host material.

The requirements enumerated in this condition must be clearly stated under "Environmental Notes" on all Project construction permit plans and building permit plans.

E. Approval of this SMA Major Permit does not constitute compliance with other City ordinances, including but not limited to the Land Use Ordinance ("LUO") and building and construction codes, or other governmental requirements, including but not limited to LUO-related approvals, and building, grading, and grubbing permit approvals, which are subject to separate review and approval. The Applicant is responsible for ensuring that the final plans for the Project approved under this SMA Major Permit comply with all applicable City ordinances and other governmental provisions and requirements; and

HONOLULU CITY COUNCIL

KE KANIHELA O KE KALANA O HONOLULU

CITY AND COUNTY OF HONOLULU

No. **26-4, CD1**

RESOLUTION

BE IT FINALLY RESOLVED that copies of this resolution be transmitted to Colette Sakoda, Environmental Planning Solutions, LLC, 945 Makaiwa Street, Honolulu, Hawai'i 96816; Roger Babcock Jr., Director of the Department of Environmental Services, 91-2060 Franklin D. Roosevelt Avenue, Kapolei, Hawai'i 96707; Laura Thielen, Director of Parks and Recreation, 1000 Ulu'ōhi'a Street, Suite 309, Kapolei, Hawai'i 96707; Dawn Takeuchi Apuna, Director of Planning and Permitting, 650 South King Street, 7th Floor, Honolulu, Hawai'i 96813; and Mary Alice Evans, Director of the State of Hawai'i Office of Planning and Sustainable Development, Attention: Coastal Zone Management Branch, P.O. Box 2359, Honolulu, Hawai'i 96804-2359.


INTRODUCED BY:

Tommy Waters (br)

DATE OF INTRODUCTION:

January 7, 2026
Honolulu, Hawai'i

Councilmembers



Prepared by: Honolulu Land Information System (HoLIS) - CS
Department of Planning & Permitting (DPP)
City and County of Honolulu

Date Prepared 10/2025

Copyright City & County of Honolulu
All Rights Reserved 2025

EXHIBIT A





EXHIBIT B **FILE NO.: 2025-SMA-75**



Prepared by: Honolulu Land Information System (HoLIS) - CS
Department of Planning & Permitting (DPP)
City and County of Honolulu

Date Prepared 10/2025

Copyright City & County of Honolulu
All Rights Reserved 2025

EXHIBIT C

JOB NO. W#-##


60% SUBMITTAL

WEST LOCH ESTATES WASTEWATER PUMP STATION UPGRADE

EWA, OAHU, HAWAI
TMK 9-1-181 001


DIVISION OF WASTEWATER ENGINEERING & CONSTRUCTION
DEPARTMENT OF ENVIRONMENTAL SERVICES
CITY & COUNTY OF HONOLULU

VICINITY MAP




VICINITY MAP

LOCATION MAP




LOCATION MAP

APPROVED



EXISTING SITE AND DEMOLITION PLAN

EXHIBIT D-1 **FILE NO.: 2025/SMA-75**








EXHIBIT D-2 **FILE NO.: 2025/SMA-75**




KAULA AE	WEST LOCH ESTATES WWPS UPGRADE EWA, OAHU, HAWAII	SITE PLAN OCTOBER 2025	1



KAULA AE	PROJECT TITLE: PUMP BUILDING ELEVATION 1 PROJECT LOCATION: WEST LOCH ESTATES WWPS UPGRADE EWA, OAHU, HAWAII TMK 9-1-181:001	PROJECT NO 2517 SCALE AS SHOWN DATE NOVEMBER 2025 FIG NO 2

EXHIBIT D-3 **FILE NO.: 2025/SMA-75**








EXHIBIT D-4 **FILE NO.: 2025/SMA-75**



PUMP STATION - SECTION A

60% SUBMITTAL



PIPING PLAN - SECTION B

60% SUBMITTAL

EXHIBIT D-5 **FILE NO.: 2025/SMA-75**




Figure 13. Wastewater pump station with a detached CMU dumpster enclosure, facing northwest.



Figure 14. CRM wall enclosure, facing southwest.





Figure 20. CRM wall enclosure with attached blue metal gate, facing north.



Figure 17. Gravel yard with diesel fuel tank and HECO enclosures, facing south.



PORTION OF
FLOOD HAZARD MAP

FIRM PANEL 15003C0326G

TAX MAP KEY: 9-1-181:001 por.

FOLDER NO.: 2025-SMA-75

Prepared by: Honolulu Land Information System (HoLIS) - CS
Department of Planning & Permitting (DPP)
City and County of Honolulu

Date Prepared: 10/2025

Copyright City & County of Honolulu
All Rights Reserved 2025

EXHIBIT F

WETLAND MAP (U.S. Fish and Wildlife Service)



EXHIBIT G **FILE NO.: 2025/SMA-75**

SOILS MAP (U.S. Department of Agriculture)

EXHIBIT H

FILE NO.: 2025/SMA-75

SEA LEVEL RISE MAP (3.2 ft. of SLR – Related High Wave Flooding by 2100)

EXHIBIT I-1 **FILE NO.: 2025/SMA-75**

SEA LEVEL RISE MAP (6.0 ft. of SLR – Passive High Tide Flooding by 2100)

EXHIBIT I-2 **FILE NO.: 2025/SMA-75**

EXHIBIT J **FILE NO.: 2025/SMA-75**

TSUNAMI EVACUATION MAP




EXHIBIT K

FILE NO.: 2025/SMA-75

CUMULATIVE PROJECTS RADIUS MAP



EXHIBIT L **FILE NO.: 2025/SMA-75**

Report Title:
Special Management Area ("SMA") Major Permit; Land Use Permit; Department of Planning and Permitting ("DPP"); Department of Environmental Services ("ENV"); Department of Parks and Recreation ("DPR"); Kapapapuhi Point Park; West Loch Community Shoreline Park; ʻEwa Beach, Oʻahu; Honouliuli, Oʻahu; Honouliuli, Oahu

The summary description of legislation appearing on this page is for informational purposes only and is not legislation or evidence of legislative intent.